Government ePublishing System

ePublishing System, Government of India

Tender Details

Date : 23-Nov-2026 05:28 PM

Print

Basic Details

Organisation Chain	Department of Health Research||Indian Council of Medical Research		
Tender Reference Number	PUR/PP 4458/E FILE 302288/2026-27		
Tender ID	2026_DoHR_858042_1		
Tender Type	Open Tender	**Form of contract**	Works
Tender Category	Works	**No. of Covers**	1
Payment Mode	Not Applicable	**Is Multi Currency Allowed For BOQ**	No
Is Multi Currency Allowed For Fee	No		

Cover Details, No. Of Covers - 1

Cover No	Cover	Document Type	Description
1	Fee/PreQual/Technical/Finance	.xls	BID DOCUMENTS

Tender Fee Details, [Total Fee in ₹ * - 0.00]

Tender Fee in ₹	0.00		
Fee Payable To	NA	**Fee Payable At**	NA
Tender Fee Exemption Allowed	NA		

EMD Fee Details

EMD Amount in ₹	0.00	**EMD Exemption Allowed**	NA
EMD Fee Type	NA	**EMD Percentage**	NA
EMD Payable To	NA	**EMD Payable At**	NA

Work /Item(s)

Title	Job work Reconstruction and upgradation of weakened Compound walls at ICMR NIV Pashan campus				
Work Description	Job work Reconstruction and upgradation of weakened Compound walls at ICMR NIV Pashan campus				
Pre Qualification Details	Please refer Tender documents.				
Tender Value in ₹	2,30,000	**Product Category**	Job Works	**Sub category**	NA
Contract Type	Tender	**Bid Validity(Days)**	180	**Period Of Work(Days)**	30
Location	Watch and Ward ICMR NIV Camp Pune	**Pincode**	411001	**Pre Bid Meeting Place**	NA
Pre Bid Meeting Address	NA	**Pre Bid Meeting Date**	NA	**Bid Opening Place**	ICMR - NATIONAL INSTITUTE OF VIROLOGY, PUNE

Critical Dates

Publish Date	23-Nov-2026 06:00 PM	**Bid Opening Date**	08-Dec-2026 03:00 PM
Document Download / Sale Start Date	23-Nov-2026 06:00 PM	**Document Download / Sale End Date**	08-Dec-2026 03:00 PM
Clarification Start Date	NA	**Clarification End Date**	NA
Bid Submission Start Date	23-Nov-2026 06:00 PM	**Bid Submission End Date**	08-Dec-2026 03:00 PM

Tender Documents

NIT Document

S.No	Document Name	Description	Document Size (in KB)
1	Tendernotice_1.pdf	NIT	1806.46

Work Item Documents

S.No	Document Type	Document Name	Description	Document Size (in KB)
1	Tender Documents	4458.pdf	Tender Documents	1806.46

Tender Inviting Authority

Name	DIRECTOR
Address	ICMR-NIV CAMP PUNE

Tender Creator Details	
Created By	Naveen Kumar
Designation	Director
Created Date	23-Nov-2026 05:27 PM

icmr | NIV
INDIAN COUNCIL OF MEDICAL RESEARCH
NATIONAL INSTITUTE OF VIROLOGY

आई सी एम आर - राष्ट्रीय विषाणु विज्ञान संस्थान
स्वास्थ्य अनुसंधान विभाग
स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार
ICMR - NATIONAL INSTITUTE OF VIROLOGY
Department of Health Research
Ministry of Health & Family Welfare, Govt. of India

Ref: Pur/PP 4458/e-file 302288/26-27

Date: 28/11/2026

Advertisement Tender Enquiry

We are interested in inviting quotation for Job Work as per details given below:

Please go through the attached **Terms and Conditions** and submit the quotation immediately addressing to **the Administrative Officer (Stores & Purchase), ICMR-National Institute of Virology, 20-A, Dr. Ambedkar Road, Pune 411 001.**

S.No.	Full description with complete specification	Qty
1	Job work, Reconstruction and Upgradation of Weakened Compound Walls at ICMR-NIV Pashan Campus **Kindly refer Annexure for scope of work**	1 Job

The above requirement is uploaded on CPP Portal (ePublishing) for open information to offer the genuine quote on the proprietary nature of the Product/Services.

Bidders are requested to quote the revised rates of GST as applicable issued by Department of Revenue, Ministry of Finance, Government of India.

The quotation super scribed as "PP 4458/2026-27- Job Work, Reconstruction and Upgradation of Weakened Compound Walls at ICMR-NIV Pashan Campus" addressed to the Director, ICMR-National Institute of Virology, 20-A, Dr. Ambedkar Road, Post box-11, Pune – 411 001 (Attention: Administrative Officer-Stores) should be either dropped at the Admin Department at NIV or sent through by Speed post / courier (with signature & seal in company letter head) latest by 08 / 12 /2026 till 3. 00P.M

Due Date to submit the offer/quotation: 08 / 12 /2026 3:00 P.M.

Thanking you,

Sincerely,

Administrative Officer (Stores & Purchase)

आई सी एम आर – राष्ट्रीय विषाणु विज्ञान संस्थान
स्वास्थ्य अनुसंधान विभाग
स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार
ICMR - NATIONAL INSTITUTE OF VIROLOGY
Department of Health Research
Ministry of Health & Family Welfare, Govt. of India

Bidders may refer to OM No. P-45021/2/2017-PP(BE-II)-Part(4) Vol.II dated 08th July 2025 for requirements vis-à-vis 'Make in India' policy

a) Eligibility: The Bidder must be a Manufacturer or its authorized Agent.

b) One Bid per Bidder: A firm shall submit only one bid either individually or as a partner of a joint venture. A firm that submits either individually or, as a member of a joint venture, more than one bid will cause all the proposals with the firms' participation to be disqualified.

c) ICMR reserves the right to cancel the bid in part or full without assigning any reason and liability on the buyer. On such cancellation the decision of the DG, ICMR will be binding and final on the subject.

d) You are requested to kindly submit your detailed quote inclusive of all breakups with discounts and all applicable taxes, duties etc., and complete address of your OEM.

e) The price quoted should be upto **ICMR- National Institute of Virology (**consignee location) inclusive of packing and forwarding charges, freight and insurance. In case of local suppliers the prices quoted should be on "Free delivery basis" at ICMR-NIV Stores. No other charges except those mentioned clearly in the quotation will be paid.

f) Prices shall be quoted in Indian Rupees only.

g) Signed / E-sign & scanned quotes through email are acceptable.

h) For hazardous chemical/item, all precautionary measure as per regulation from the point of transportation/ handling/ storage/ safety/ health/ environment to be undertaken/ specified before dispatch. During dispatch, proper symbol for the hazard/ MSDS/ Batch No./ date of manufacturing/ Gross Weight/ Net Weight/ shelf Life etc are to be written/ printed/ pasted on the body of the packing.

i) **Payment Terms:** 100% payment shall be made after receipt of complete goods/Equipment in good condition, acceptance and successful installation of goods/Equipment. This payment is subject to recoveries, if any, either on account of statutory deduction/ taxes/ Liquidated Damages, if any and non-rectification of defects/ deficiencies not attended by the Supplier or otherwise.

j) Delivery Time: Maximum within 3 weeks. However, please indicate the delivery period clearly in the Quote.

k) Penalty Clause: Any delay in dispatching the material may attract penalty @ 0.5% per week subject to a maximum of 10% of the total value of order.

l) Insurance: The supplier shall make all necessary arrangements for insuring the goods against loss or damage incidental to manufacture or acquisition, transportation, storage and delivery.

m) Address of Consignee (Place of Work) : Watch and Ward, ICMR-NIV, Camp Road, Pune- 411001

n) Validity of the quotation: Minimum 180 days validity from the date of quote to be provided.

o) GST will be applicable as per the latest GoI notification.

p) If the material is perishable in nature, sufficient dry ice/gel should be added, so that sustainability of the material remains for at least 10 days.

q) Bidder is requested to give undertaking Certificate regarding land border "I/ We have read the clause issued by Government of India regarding restrictions on procurement from a bidder of a country which shares a land border with India; I/ We certify that the bidder is not from such a country or, if from such a country, have been registered with the Competent Authority"

Signature of the Bidder with seal

UNDERTAKING FOR REASONABLE PRICE ANNEXURE-I

This is to Certify that we have offered the possible reasonable prices vide our Quote No. _____ dated _____ in response to ICMR-NIV Enquiry No. _____, Dated _____ and we further undertake that we will not offer less than the offered rates during the validity period to any other State / Central / PSU / Autonomous Bodies / Universities / R&D Institutes / Pharmaceutical Laboratories / Public Limited Companies.

Place:

Date:

Sign. of Bidder with Seal

Scope of Work and Technical Specifications: Reconstruction and Upgradation of Weakened Compound Walls at ICMR-NIV Pashan Campus

The work entails the complete dismantling of the existing 5-foot-high wall and 4-foot barbed wire fencing at two sections total length 80 feet and the construction of a robust, upgraded 6-foot-high stone masonry compound wall topped with 4 feet of heavy-duty concertina wire fencing (total height: 10 feet per section), ensuring enhanced campus security and structural longevity.

Scope of Work (SOW)

Phase 1: Site Clearance, Dismantling & Demolition

- Safe Dismantling: Carefully dismantle and remove the existing damaged stone masonry and concrete coping/pillars across the two designated sections (50 RFT and 30 RFT, totalling 80 RFT).
- Fencing Removal: Dismantle existing deteriorated angle iron posts and barbed wire fencing (4 feet height).
- Debris Disposal: Clear all rubble, damaged stone, old concrete debris, and vegetative growth from the foundation alignment and transport debris outside the campus operational areas to designated dumping yards as per municipal/institutional norms.

Phase 2: Earthwork & Foundation

- Excavation: Excavate foundation trenches in soil/rock to the required depth and width as per CPWD/structural design specifications to ensure stable load-bearing capacity for the new stone wall.
- PCC Bedding: Lay a leveling course of Plain Cement Concrete (PCC 1:4:8 or 1:3:6) of appropriate thickness (min. 150 mm) over the compacted trench bed.

Phase 3: Stone Masonry Superstructure Construction

- Random Rubble (RR) / Coursed Rubble Stone Masonry: Construct the new compound wall using robust, durable, locally sourced hard dressed/undressed stone blocks in cement mortar (1:6 or specified ratio).
- Wall Dimensions:

- Total length: 80 RFT (50 RFT + 30 RFT).
- Height: 6 feet above plinth level.
- Thickness: 2 feet maintaining plumb

- Coping Band & Pillars: Provide reinforced cement concrete (RCC M20/M25) band and pilasters/columns at regular intervals and at top coping to tie the masonry securely and provide rigid anchor points for security fencing uprights.

Phase 4: Fencing & Security Upgradation

- MS Angle Posts: Fabricate and erect robust structural steel angle posts (e.g., ISA 50x50x6 mm or heavier) securely embedded into the RCC top band, standing 4 feet clear above the stone wall.
- Concertina Wire Fencing: Install high-tensile galvanized barbed concertina coil fencing (dia. 600 mm or as specified) securely lashed and clipped to horizontal support lines and Y-brackets/extension arms fixed to the MS angle posts, replacing the old barbed wire.

Phase 5: Finishing & Painting

- Plastering / Pointing: Rake out joints and finish stone masonry with neat flush/V-pointing or cement plaster as per campus aesthetics.
- Anti-Corrosive Treatment: Apply red oxide primer and dual coats of enamel paint to all MS angle posts and fencing hardware to prevent rusting.

Technical Specifications & Material Standards

Component	Specification Standard
Stone Masonry	Hard, sound, durable quarry stone conforming to CPWD specs; laid in CM 1:6.
Cement & Sand	Ordinary Portland Cement (OPC 43/53 grade) or PPC conforming to IS:1489/IS:8112; clean, coarse river/M-sand free from silt and organic impurities.
Concrete (PCC/RCC)	PCC mix (1:4:8) for foundation bed; RCC M25 grade for coping bands, tie beams, and vertical columns using machine-mixed vibrated concrete.

Component	Specification Standard
Reinforcement Steel	TMT Fe-500 grade bars conforming to IS:1786.
Structural Steel Posts	Hot-rolled mild steel angles (minimum 50x50x6 mm) with base plate anchoring.
Concertina Fencing	Hot-dip galvanized spring steel concertina coil (minimum 600 mm diameter, 50 clips per coil, high tensile core wire).
Painting	Synthetic enamel over red oxide primer for metal works.

Note: Visit site before submitting quote. Payment will be done after satisfactory completion of work as per engineer in charge.