आई सी एम आर – राष्ट्रीय विषाणु विज्ञान संस्थान
स्वास्थ्य अनुसंधान विभाग
स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार
ICMR - NATIONAL INSTITUTE OF VIROLOGY
Department of Health Research
Ministry of Health & Family Welfare, Govt. of India

Ref: Pur/PP 4175/e-file 300280/26-27

Date: 13-11-2026

Advertisement Tender Enquiry

We are interested in Procurement of Products as per details given below:

Please go through the attached **Terms and Conditions** and submit the quotation immediately addressing to **the Administrative Officer (Stores & Purchase), ICMR-National Institute of Virology, 20-A, Dr. Ambedkar Road, Pune 411 001.**

S.No.	Full description with complete specification	Qty
1	Job work, WPC Wall Panelling & Lustre Paint work	1 Job

The above requirement is uploaded on CPP Portal (ePublishing) for open information to offer the genuine quote on the proprietary nature of the Product/Services.

Bidders are requested to quote the revised rates of GST as applicable issued by Department of Revenue, Ministry of Finance, Government of India.

The quotation super scribed as "PP 4175/2026-27- Job Work, WPC Wall Panelling & Lustre Paint work" addressed to the Director, ICMR-National Institute of Virology, 20-A, Dr. Ambedkar Road, Post box-11, Pune – 411 001 (Attention: Administrative Officer-Stores) should be either dropped at the Admin Department at NIV or sent through by Speed post / courier (with signature & seal in company letter head) latest by 26/11/2026 till 3. 00P.M

07/12/2026

Due Date to submit the offer/quotation: 26/11/2026 3:00 P.M.

Thanking you,

07/12/2026.

Sincerely,

Administrative Officer (Stores & Purchase)

INDIAN COUNCIL OF MEDICAL RESEARCH
Serving the nation since 1911
NATIONAL INSTITUTE OF VIROLOGY

आई सी एम आर – राष्ट्रीय विषाणु विज्ञान संस्थान
स्वास्थ्य अनुसंधान विभाग
स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार
ICMR - NATIONAL INSTITUTE OF VIROLOGY
Department of Health Research
Ministry of Health & Family Welfare, Govt. of India

Bidders may refer to OM No. P-45021/2/2017-PP(BE-II)-Part(4) Vol.II dated 08th July 2025 for requirements vis-à-vis 'Make in India' policy

a) Eligibility: The Bidder must be a Manufacturer or its authorized Agent.

b) One Bid per Bidder: A firm shall submit only one bid either individually or as a partner of a joint venture. A firm that submits either individually or, as a member of a joint venture, more than one bid will cause all the proposals with the firms' participation to be disqualified.

c) ICMR reserves the right to cancel the bid in part or full without assigning any reason and liability on the buyer. On such cancellation the decision of the DG, ICMR will be binding and final on the subject.

d) You are requested to kindly submit your detailed quote inclusive of all breakups with discounts and all applicable taxes, duties etc., and complete address of your OEM.

e) The price quoted should be upto **ICMR- National Institute of Virology (**consignee location) inclusive of packing and forwarding charges, freight and insurance. In case of local suppliers the prices quoted should be on "Free delivery basis" at ICMR-NIV Stores. No other charges except those mentioned clearly in the quotation will be paid.

f) Prices shall be quoted in Indian Rupees only.

g) Signed / E-sign & scanned quotes through email are acceptable.

h) For hazardous chemical/item, all precautionary measure as per regulation from the point of transportation/ handling/ storage/ safety/ health/ environment to be undertaken/ specified before dispatch. During dispatch, proper symbol for the hazard/ MSDS/ Batch No./ date of manufacturing/ Gross Weight/ Net Weight/ shelf Life etc are to be written/ printed/ pasted on the body of the packing.

i) **Payment Terms:** 100% payment shall be made after receipt of complete goods/Equipment in good condition, acceptance and successful installation of goods/Equipment. This payment is subject to recoveries, if any, either on account of statutory deduction/ taxes/ Liquidated Damages, if any and non-rectification of defects/ deficiencies not attended by the Supplier or otherwise.

j) Delivery Time: Maximum within 3 weeks. However, please indicate the delivery period clearly in the Quote.

k) Penalty Clause: Any delay in dispatching the material may attract penalty @ 0.5% per week subject to a maximum of 10% of the total value of order.

l) Insurance: The supplier shall make all necessary arrangements for insuring the goods against loss or damage incidental to manufacture or acquisition, transportation, storage and delivery.

m) Address of Consignee (Place of Work) : Watch and Ward, ICMR-NIV, Camp Road, Pune- 411001

n) Validity of the quotation: Minimum 180 days validity from the date of quote to be provided.

o) GST will be applicable as per the latest GoI notification.

p) If the material is perishable in nature, sufficient dry ice/gel should be added, so that sustainability of the material remains for at least 10 days.

q) Bidder is requested to give undertaking Certificate regarding land border "I/ We have read the clause issued by Government of India regarding restrictions on procurement from a bidder of a country which shares a land border with India; I/ We certify that the bidder is not from such a country or, if from such a country, have been registered with the Competent Authority"

Signature of the Bidder with seal

UNDERTAKING FOR REASONABLE PRICE ANNEXURE-I

This is to Certify that we have offered the possible reasonable prices vide our Quote No. _____ dated _____ in response to ICMR-NIV Enquiry No. _____, Dated _____ and we further undertake that we will not offer less than the offered rates during the validity period to any other State / Central / PSU / Autonomous Bodies / Universities / R&D Institutes / Pharmaceutical Laboratories / Public Limited Companies.

Place:

Date:

Sign. of Bidder with Seal

Annexure

Work: WPC Wall Panelling & Lustre Paint Painting work in Dinning Hall

Location: ICMR-NIV Pashan Campus, Pune

Areas: Wall Area = 750 Sq. Ft. & Ceiling Area = 800 Sq. Ft.

Scope of Work (SOW):

The updated scope of work covers all labour, scaffolding, framework, putty, priming, painting, and materials required for executing WPC panelling on walls and a premium Lustre paint finish on the false ceiling.

1.1 Wall Surface Preparation & Anti-Damp Treatment (750 Sq. Ft.):

1. Inspect wall surfaces, scrape off loose/peeling paint, and treat damp areas with anti-fungal biocide solutions to prevent future mold growth behind panels.
2. Fix damp-proof polyethylene vapour barrier sheets where necessary to isolate masonry dampness from internal framing.

1.2 WPC Wall Panelling Installation (750 Sq. Ft.):

1. Erect a heavy-duty, rust-proof commercial-grade aluminum grid framework securely anchored to the walls.
2. Install exterior/interior grade WPC fluted or louvered panels onto the wall grid using concealed interlocking clips and high-strength polyurethane structural adhesive. Neatly trim edges and joints.

1.3 Lustre Painting Execution (800 Sq. Ft.):

1. Putty & Priming: Apply two coats of water-resistant acrylic wall putty to level joints and surface imperfections, followed by one coat of interior primer. Rub down with fine abrasive paper to achieve a smooth, mirror-like base.
2. Lustre Paint Application: Apply two or more coats of premium solvent-based or high-end water-based lustre paint (silky sheen finish) using professional rollers/brushes to ensure uniform gloss, scrub ability, and a luxurious institutional ceiling appearance.

1.4 Site Clearance & Handover:

Clean all panels, remove protective films, clear debris from the site, and hand over the finished space in a pristine condition.

3. Material Specifications :

To ensure maximum durability, moisture resistance, and an elegant finish, the following technical specifications are laid down:

Component	Technical Specification
WPC Wall Panels	High-Density WPC (Wood Plastic Composite) extruded fluted/louvered panels (60% virgin wood fiber, 30% polymer resins, 10% additives). Thickness: 12mm–15mm
False Ceiling Board	12mm Moisture-Resistant (MR) Gypsum Board or Calcium Silicate Board screw-fixed onto a heavy-duty GI framework.
Lustre Paint & Primer	Premium Grade Solvent/Water-Based Lustre Enamel (e.g., Asian Paints Royale Lustre or equivalent grade) providing a smooth, high-sheen, scrub able, and stain-resistant finish, backed by an anti-fungal wall primer.
Framing Material	Heavy-duty Aluminium Hollow Section Grid for walls and Galvanized Iron (GI) Framing for the ceiling suspension system.
Adhesives & Fasteners	Anti-fungal structural PU adhesive, drywall joint tape, anti-rust screws, and mounting clips.

Note:

1. Do site visit before submitting the quote.
2. Payment will be done after submission of satisfactory completion certificate from Engineer in charge.